

> 2019 PTC Paving Award - Lindy






> Agenda

- HMA results for 2018
- Spec Changes
- HMA Designs for 2019
- Warm Mix project & Fiber Modified HMA project
- Materials Lab update
- Questions

HMA TONS PLACED



- ➤ Samples Tested 590,393 ton
- 575 lots tested
- 90% of Lots receive full payment
- 56 failed Lots
 - 17 Lots were defective (14,760 ton)
 - 3 Lots were at 50% pay
 - 1 Lot at 0% pay
 - 13 Lots were removed and replaced (11,738 ton)

YEARLY HMA PAYMENT %					
	2014	2015	2016	2017	2018
# of Lots tested	602	779	844	795	575
Lots @ 100% pay	88%	90%	94%	90%	90%
% of Defective lots	4.3%	3.8%	2.6%	3.2%	3.0%
HMA FAILURES					
	2014	2015	2016	2017	2018
Low AC	5	2	2	2	2
High AC	2	5	0	9	1
Low #200	0	0	0	2	0
High #200	0	3	0	6	6
Low Voids	34	33	18	30	34
High Voids	28	38	37	21	11
Low/High Density	11/0	5/0	10/0	8/0	4/0

> HMA (tons) shipped by Size

- 12.5mm 284,442
- (SMA 12.5mm 88,734)
- 25mm 130,552
- 19mm 115,830
- RB25mm 48,181
- 9.5mm 11,388
- \rightarrow ATPBC 46,870
- ➤ Certified 74,027
- TOTAL shipped 711,290 ton

➤ Average Density by Size

- 9.5mm 94%
- 12.5mm 94%
- SMA (12.5mm) 95%
- 19mm 95%
- 25mm 95%
- RB25mm 96%
- > Avg. Density 95%

(k) Joints.

1. Longitudinal Joints.

Seal all completed wearing surface transverse joints and all longitudinal joints between adjacent resurfaced lanes, medians and shoulders in the same calendar year in which the joint was completed. Seal all joints with rubberized joint sealing material meeting ASTM D6690-Type I from a manufacturer in Bulletin 15 as specified in Section 705.4(c). The sealing band must be 4" to 6" in width evenly applied by a disk or squeegee across the joint. The sealing band must be 4" to 6" in width evenly applied by a disk or squeegee across the joint.

2. Mixture Lot Acceptance (Standard Construction).

2.d. Lot Termination. The Contractor may request to terminate a lot if an issue affecting quality of the material is discovered. The request must be made in writing to the Representative, stating the reason for termination and the affected tonnage, which shall be removed and replaced at no cost to the Commission. Before paving resumes, the Contractor must provide written notification to the Representative that corrections have been made to the original cause for the lot termination. When paving resumes, a new lot number will be used. Any samples taken from the terminated lot shall be forwarded to the materials representative.

> HMA Designs for 2019


- No Virgin designs required in 2019
- HMA designs samples are verified at our Lab
 - PENNDOT roads need PENNDOT approved designs
- Field Core size has been a problem....
 - 4.c. Density Acceptance Samples. The Inspector will select three different sample locations in each sublot according to PTM No.1. With the Inspector present and in accordance with PTM 729, drill (1) 6-inch diameter core at each random location as soon as possible but no later than 24 hours following placement.

- Warm Mix Project
- A-115.00R001-3-02
 - ○19mm 27,987 ton
 - 34 Lots / 32 Lots @ 100% payment
 - 1 Lot @ 94% payment for low voids
 - 1 Lot defective for low voids
 - Density avg. was 95%
 - ○12.5mm 21,029 ton
 - 21 lots / 20 lots with 100% payment
 - 1 Lot @ 94% payment for low Voids
 - Density avg. was 94%

> HMA Fiber Modified 12.5mm

- A-076.00R001-3-02
 - Forta-Fiber was added to 12.5 mm material
 - 1 # bag per ton
 - Material will be placed on a total of 2.3 miles in each direction and each lane at specific mileposts
 - ○4,466 ton required 2,161 ton was placed in 2018
 - o 2 Lots / 2 Lots @ 100% payment
 - Samples lifted for testing at PSU by the Producer/FORTA

FORTA FIBERS (A-076.00R001-3-02) Locust Ridge Plant - 1 # Bag/ton






➤ Performance Testing...





> Permeater Test







> PTC Material Managers

- East (300 358 / A-20 A-130)
 - Steve Havrilla
- Central (146 300)
 - Brian Wible
- West (0 146)
 - Chris Forry
- Materials Lab (113.8 EB)
 - Brian Paroda

Thank You for your attention... Have a SAFE Construction season!!

Any Questions?

